


# PROPOSED MEDICAL OFFICE BUILDING

PREPARED FOR ORTHO SAYBROOK, LLC 52 SPENCER PLAIN ROAD (CT ROUTE 166) OLD SAYBROOK, CONNECTICUT





DRAWING INDEX:				
TITLE	DWG. NO.	SHEET	NO.	
SITE PLAN	SP-1	1	OF	13
LANDSCAPING & LIGHTING PLAN	LL-1	2	OF	13
GRADING, UTILITIES & SEPTIC SYSTEM PLAN	GUS-1	3	OF	13
SOIL EROSION & SEDIMENTATION CONTROL PLA	AN SES-1	4	OF	13
SEPTIC DESIGN CRITERIA & SOIL TESTING DATA	SDC-1	5	OF	13
CONSTRUCTION DETAILS (SEPTIC)	CD-1	6	OF	13
CONSTRUCTION DETAILS	CD-2	7	OF	13
CONSTRUCTION DETAILS (WATER)	CD-3	8	OF	13
CONSTRUCTION DETAILS (DRAINAGE)	CD-4	9	OF	13
CONSTRUCTION DETAILS	CD-5	10	OF	13
E&S CONTROL NARRATIVE AND DETAILS	ES-1	11	OF	13
E&S CONTROL DETAILS	ES-2	12	OF	13
SOIL SAMPLE DATA	SSD-1	13	OF	13



	1	5/14/2024	REVISIONS PER TOWN ENGINEER'S COMMENTS, MISC.	RG
<b>J</b> (	#	DATE	DESCRIPTION	BY

### FOR REVIEW - NOT FOR CONSTRUCTION

Approved	by the Old Saybrook Zoning	Commission
 Title	 Signature	

### LAND SURVEYOR

ANNINO SURVEY, LLC DAVID A. ANNINO, L.S. 222 OLD BOSTON POST ROAD, SUITE 3 OLD SAYBROOK, CT 06475

### **BUILDING ARCHITECT**


BORGHESI BUILDING & ENGINEERING CO. INC. 2155 EAST MAIN STREET TORRINGTON, CT 06790

# CIVIL ENGINEER

INDIGO LAND DESIGN, LLC JOE WREN, P.E. 40 ELM STREET, 2ND FLOOR OLD SAYBROOK, CT 06475

## PROPERTY OWNER/APPLICANT

ORTHO SAYBROOK, LLC 430 SAYBROOK ROAD, SUITE 100 MIDDLETOWN, CT 06457



OLD SAYBRO	OK GATEWAY BUIS	SNESS 'B-4' DISTRICT
ITEM	REQUIRED	PROPOSED
MIN. LOT AREA	20,000 S.F.	289,459± S.F. (GROSS) 228,584± S.F. (NET) (1)
MIN. FRONTAGE	50 FT.	432.68 FT. (EXIST.)
STREET LINE SETBACK	50 FT.	310.9± FT. (PROP. BUILDING)
SIDE YARD SETBACK (NORTH BOUNDARY)	20 FT.	84.7± FT. (PROP. BUILDING)
SIDE YARD SETBACK (SOUTH BOUNDARY)	20 FT. 0 FT. (2)	63.4± FT. (PROP. BUILDING)
REAR YARD SETBACK (EAST BOUNDARY)	20 FT.	159.5± FT. (PROP. BUILDING)
MAX. # OF STORIES	2 1/2 STORIES	1 STORY (PROP. BUILDING)
MAX. BUILDING HEIGHT	35 FT.	33.8± FT. (PROP. BUILDING) (3)
MAX. GROSS FLOOR AREA	60% (137,150 S.F.)	10.4% (23,819± S.F.) (4)
MAX. BUILDING/ STRUCTURE COVERAGE	40% (91,433 S.F.)	10.7% (24,441± S.F.) (5)
TOTAL LOT COVERAGE	70% (160,008 S.F.)	37.9% (86,710± S.F.) (6)

- MIN. LOT AREA (I.E., NET LOT AREA) EQUALS GROSS LOT AREA LESS WEILANDS. NET LOT AREA WAS USED TO COMPUTE MAX. GROSS FLOOR AREA AND MAX. BUILDING/STRUCTURE NET LOT AREA =  $289,459\pm$  S.F. (GROSS) -  $60,875\pm$  S.F. (WETLANDS) =  $228,584\pm$  S.F.
- (2) PER SECTION 68.1.2.5, NO SETBACK IS REQUIRED FROM RAILROAD RIGHT-OF-WAYS IN
- (3) BUILDING HEIGHT WAS MEASURED FROM THE MAX. ROOF RIDGE DOWN TO AVERAGE EXISTING GRADE AT THE PERIMETER OF THE BUILDING. MAX. BLDG. HEIGHT = EL.  $56.3\pm$  (MAX. RIDGE) - EL.  $22.5\pm$  (AVG. EX. GRADE) =  $33.8'\pm$ (NOTE: BUILDING HEIGHT IS 26.3± FT. AS MEASURED FROM PROPOSED FINISHED GRADE)
- MAX. G.F.A. =  $22,381\pm$  S.F. (BUILDING AREA) +  $1,439\pm$  S.F. (ENTRIES) = 23,820 S.F.
- (5) BUILDING/STRUCTURE COVERAGE INCLUDES GROSS FLOOR AREA PLUS TRANSFORMER. MAX. BLDG./STRUCT. COVERAGE =  $23,820\pm$  S.F. (MAX. G.F.A.) + 477± (RETAINING WALLS)

#### + 144± (ABOVE GROUND UTILITIES) $= 24,441 \pm S.F.$

(6) MAX. TOTAL LOT COVERAGE INCLUDES ALL BUILDING/STRUCTURE COVERAGE PLUS THE PAVED DRIVE, WALKS, WALLS AND OTHER IMPERVIOUS AREAS. TOTAL LOT COVERAGE =  $24,441\pm$  S.F. (BLDG./STRUCT. COVERAGE)

+ 62,269  $\pm$ S.F. (DRIVE, WALKS, ETC.) = 86,710 $\pm$  S.F.

PARKING REQUIREMENTS				
ITEM	REQUIRED	PROPOSED		
MINIMUM EQUIRED PARKING SPACES	MEDICAL OFFICE:  1 SPACE PER 200 S.F. G.F.A.  23,820± S.F. x 1 SPACE PER 200 S.F. = 120 SPACES	120 SPACES (INCLUDES 5 HANDICAP PARKING SPACES)		

FOR REVIEW - NOT FOR CONSTRUCTION

Approved by the Old Saybrook Zoning Commission

Signature

APRIL 4, 2024 SCALE: 1"=40' DRAWN BY:


CHECKED BY:

DWG. NO.:

SHEET NO.:

1 of 13 JOB. NO :

Date



### **LANDSCAPING NOTES:**

- 1. LANDSCAPING SHOWN IS FOR REFERENCE ONLY. REFER TO LANDSCAPE PLANS FOR LANDSCAPE
- 2. ALL PLANTING LOCATIONS ARE APPROXIMATE AND MAY BE ADJUSTED DUE TO ACTUAL FIELD CONDITIONS.
- 3. ALL PLANTINGS MUST BE IN HEALTHY, GROWING CONDITION WHEN INSTALLED. ALL PLANTINGS SHALL BE GUARANTEED FOR A MINIMUM OF ONE YEAR FROM THE INSTALLATION DATE.
- 4. ALL TREES SHALL BE PLANTED IN ACCORDANCE WITH STANDARD LANDSCAPING PRACTICES. PLANTINGS SHOULD BE INSTALLED BETWEEN MARCH 15 AND JUNE 15 OR BETWEEN SEPTEMBER 15 AND NOVEMBER 15,
- 5. ALL UTILITY LOCATIONS SHALL BE MARKED PRIOR TO INSTALLATION OF TREES AND SHRUBS. CONTACT CALL BEFORE YOU DIG 800-922-4455. THE LANDSCAPING CONTRACTOR SHALL NOT BEGIN WORK UNTIL THE LOCATIONS OF ALL UNDERGROUND UTILITIES ARE VERIFIED AND MARKED IN THE FIELD.
- 6. PROPOSED GROUNDCOVER AROUND ALL NEW TREES AND SHRUBS SHALL BE HEMLOCK OR CEDAR MULCH OR EQUIVALENT (SEE DETAILS).

- 1. REFER TO LIGHTING PLANS PREPARED BY LITHONIA LIGHTING FOR LIGHTING DETAILS.
- 2. MAXIMUM TOTAL HEIGHT OF LIGHT POLES AND FIXTURES SHALL BE 14 FEET FROM FINISHED GRADE. CONCRETE LIGHT POLE BASES SHALL BE FLUSH WITH THE GROUND SURFACE AND PAINTED A DARK COLOR. LIGHT POLES SHALL CONFORM TO ALL LIGHT POLE MANUFACTURER REQUIREMENTS.
- 3. ALL LIGHT POLES SHALL BE A MINIMUM OF 5 FEET FROM THE EDGE OF PAVEMENT.
- ELECTRICAL SERVICES AND CONNECTIONS FOR SITE LIGHTING TO AND FROM THE BUILDING ELECTRICAL ROOM ARE NOT SHOWN ON THIS PLAN. OPTIMUM ROUTES SHALL BE SELECTED BY THE CONTRACTOR AND REVIEWED AND APPROVED BY THE OWNER PRIOR TO INSTALLATION.
- 5. OPTIMUM FIXTURE HEAD ORIENTATION TO BE SET BY SITE LIGHTING CONTRACTOR.
- 6. FINAL LIGHT FIXTURES, POLES AND ACCESSORIES SHALL BE FULL CUTOFF AND SELECTED AND APPROVED BY PROPERTY OWNER AND TOWN OF OLD SAYBROOK PRIOR TO INSTALLATION.
- 7. NO FREESTANDING OR BUILDING SIGNS ARE PROPOSED AT THIS TIME.

- 1. ONE FREESTANDING SIGN IS ALLOWED PER LOT. THE FREESTANDING SIGN SHALL HAVE A MAXIMUM AREA OF 50 S.F. THE SIGN'S SUPPORT STRUCTURE SHALL NOT EXCEED 8 FEET IN HEIGHT AND THE MAXIMUM SIGN HEIGHT SHALL NOT EXCEED 10 FEET.
- THE FREESTANDING SIGN SHALL BE 10 FEET MIN. FROM THE STREET LINE AND 5 FEET MIN. FROM THE REAR AND OTHER PROPERTY LINES.
- 3. ONE WALL SIGN IS ALLOWED PER TENANT. THE WALL SIGN SHALL NOT EXCEED 10% OF THE WALL AREA OR
- 4. FREESTANDING SIGNS AND WALL SIGNS MAY BE ILLUMINATED AS ALLOWED IN THE B-4 ZONING DISTRICT.
- 5. REFER TO PROJECT ARCHITECTURAL PLANS FOR SIGN DETAILS.

LANDSCAPING DATA TABLE						
OLD SA	NESS B-4 DISTRICT					
ITEM	REQUIRED	PROPOSED				
MINIMUM LANDSCAPE AREA (SECTION 63.1)	25% (72,365 S.F.)					
MINIMUM NUMBER OF TREES (SECTION 63.1)	12 TREES / ACRE 12 TREES x 6.65 AC. = 80 TREES	69.2% OF THE TOTAL LOT AREA IS				
FRONT LANDSCAPING (SECTION 63.3)	MIN. WIDTH = 25 FT.  1 TREE / 40 FT. OF FRONTAGE 432 FT. / 40 FT. = 11 TREES	GREEN AREA & WOODED AREA  REFER TO LANDSCAPE PLANS  (SEE GENERAL NOTE #6)				
PERIMETER LANDSCAPING (SECTION 63.4)	MIN. WIDTH = 10 FT.  1 EVERGREEN TREE SPACED 10' O.C. 758± FT. / 10 FT. = 76 TREES (1)	(SEE SENEIVAL NOTE #0)				
INTERIOR PARKING LOT LANDSCAPING (SECTION 63.5)	1 ISLAND FOR EVERY 10 PARKING SPACES (20 S.F. MIN. LANDSCAPED) MIN. 100 S.F. LANDSCAPED AREA 10' MIN DEPTH					

	LIGHTING SCHEDULE							
SYMBOL	LABEL	QUANTITY	ITEM	COLOR TEMP.	INTENSITY			
0	D	12	BUILDING DROP SOFFIT LIGHT	3,000K	923 LUMENS			
	W3	6	BUILDING WALL MOUNTED LIGHT	3,000K	5,078 LUMENS			
	W4	4	BUILDING MOUNTED WALL PACK	3,000K	5,171 LUMENS			
<b>\\ \_</b> =	S3	1	POLE MOUNTED LIGHT	3,000K	5,383 LUMENS			
<b>Ģ</b> •	S3H	6	POLE MOUNTED LIGHT	3,000K	3,915 LUMENS			
<b>-</b> ☆-	S4-2	3	POLE MOUNTED DOUBLE LIGHT	3,000K	5,463 LUMENS			
<b>\rightarrow</b> -	S4H	4	POLE MOUNTED LIGHT	3,000K	4,043 LUMENS			
<b>\ODE</b>	S5	1	POLE MOUNTED LIGHT	3,000K	5,637 LUMENS			

\*OR EQUIVALENT - SEE DETAIL.

FOR REVIEW - NOT FOR CONSTRUCTION

Signature

Date

Approved by the Old Saybrook Zoning Commission


APRIL 4, 2024 SCALE: 1"=40'

ANDS

DRAWN BY:

CHECKED BY: DWG. NO.:

SHEET NO.: 2 of 13 JOB. NO :




◇Ⅱ


APRIL 4, 2024

DRAWN BY:

DWG. NO.: GUS-1

SHEET NO .: 3 of 13





### DEEP TEST PIT DATA

DATE: 3/4/2024 EXCAVATED BY: DOWNIE'S SEPTIC & EXCAVATION WITNESSED BY: JOE WREN, P.E. (INDIGO) MELISSA HOWLEY (CRAHD) RECORDED BY: ROBERT RUSSO, C.P.S.S.

EXIST. GRADE ELEV. =  $20.2\pm$ 

TOPSOIL, DARK BROWN FINE SANDY LOAM SUBSOIL, YELLOW-BROWN FINE SANDY LOAM 47"-88"

MOTTLING & 23" (ELEV.= $18.3\pm$ ) GROUNDWATER SEEPAGE @ 40" (ELEV.=16.9±) ROOTS TO 29"

RED-BROWN SAND & GRAVEL W/ COBBLES

### TP #202

EXIST. GRADE ELEV. =  $19.9\pm$ 

TOPSOIL, DARK BROWN FINE SANDY LOAM SUBSOIL, BROWN VERY FINE SANDY LOAM

31"-71" BROWN & RED-BROWN SAND & GRAVEL MOTTLING & 19" (ELEV.=18.3±) GROUNDWATER SEÈPAGE @ 27" (ELEV.=17.7±)

ROOTS TO 21"

TP #203 EXIST. GRADE ELEV. =  $21.7\pm$ 

TOPSOIL, VERY DARK BROWN FINE SANDY LOAM SUBSOIL, YELLOW-BROWN VERY FINE SANDY

24"-91" RED-BROWN SAND & GRAVEL W/ COBBLES MOTTLING & 22" (ELEV.=19.9 $\pm$ ) GROUNDWATER SEEPAGE @ 24" (ELEV.=19.7±)

#### TP #204

ROOTS TO 22"

EXIST. GRADE ELEV. =  $19.2\pm$ 

TOPSOIL, DARK BROWN VERY FINE SANDY LOAM

SUBSOIL, BROWN FINE SANDY LOAM 44"-86"

RED-BROWN SAND & GRAVEL W/ COBBLES MOTTLING & 23" (ELEV.= $17.3\pm$ )

GROUNDWATER SEEPAGE @ 52" (ELEV.=14.9±) ROOTS TO 23"

#### TP #205 EXIST. GRADE ELEV. = $20.8\pm$

TOPSOIL, DARK BROWN VERY FINE SANDY LOAM SUBSOIL, YELLOW-BROWN FINE SANDY LOAM BROWN SAND & GRAVEL W/ COBBLES, STONES

MOTTLING & 27" (ELEV.=18.6±) GROUNDWATER SEEPAGE @ 30" (ELEV.=18.3±) ROOTS TO 33"

### TP #206

EXIST. GRADE ELEV. =  $26.8\pm$ 

TOPSOIL, BROWN VERY FINE SANDY LOAM SUBSOIL, YELLOW-BROWN SANDY LOAM BROWN SANDY LOAM W/ LITTLE GRAVEL,

COBBLES & STONES MOTTLING & 34" (ELEV.= $24.0\pm$ ) GROUNDWATER SEEPAGE @ 40" (ELEV.=23.5±) NO LEDGE ROOTS TO 38"

#### TP #207

EXIST. GRADE ELEV. =  $25.7\pm$ 

TOPSOIL, VERY DARK BROWN FINE SANDY LOAM SUBSOIL, YELLOW-BROWN FINE SANDY LOAM DENSE BROWN SANDY LOAM W/ LITTLE GRAVEL, COBBLES & STONES

MOTTLING & 24" (ELEV.=23.7±) GROUNDWATER SEEPAGE @ 27" (ELEV.=23.5±) NO LEDGE ROOTS TO 28"

### TP #208

NO LEDGE

ROOTS TO 29"

EXIST. GRADE ELEV. =  $25.5\pm$ 

TOPSOIL, VERY DARK BROWN FINE SANDY LOAM SUBSOIL, YELLOW-BROWN FINE SANDY LOAM 18"-95" BROWN SANDY LOAM W/ COBBLES & STONES MOTTLING & 18" (ELEV.= $24.0\pm$ )

GROUNDWATER SEEPAGE @ 67" (ELEV.=19.9±)

#### PERCOLATION TEST DATA DATE: 3/4/2024

CONDUCTED BY: RAY MALINOWSKI (INDIGO) PERC A

DEPTH: 19" DEPTH DROP PERC RATE (INCHES) (INCHES) (MIN./INCH) (MINUTES) 0 @ 8 --- ---6 @ 11 3/4 3 3/4 1.6 12 @ 14 1/2 2 3/4 2.2 18 @ 16 1/2 2 24 @ 18 1 1/2 4.0 (LESS THAN 3" WATER REMAINING IN HOLE)

### PERCOLATION TEST DATA

PERCOLATION RATE = 4.0 MIN./INCH

DATE: 3/4/2024 CONDUCTED BY: RAY MALINOWSKI (INDIGO)

#### PERC B DEPTH: 22"

TIME MINUTES)		DEPTH (INCHES)	DROP (INCHES)	PERC RATE (MIN./INCH)
0	@	9		
6	@	10 1/2	#####	###
12	@	11 1/4	3/4	8.0
18	@	11 3/4	1/2	12.0
24	@	12 1/4	1/2	12.0
30	0	12 3/4	3 3/4	8.0
36	0	13 1/4	1/2	12.0
42	0	14	3/4	8.0
48	0	14 3/8	3/8	16.0
54	@	14 3/4	3/8	16.0
60	@	15 1/8	3/8	16.0

#### PERCOLATION RATE = 16.0 MIN./INCH

### SANITARY SYSTEM DESIGN CRITERIA

DESIGN	BUILDING USE	REQUIRED	LEACHING	EFFECTIVE	LEACHING	REQUIRED TANK	TANK CAPACITY
PERC RATE		LEACHING AREA	SYSTEM TYPE	LEACHING AREA	AREA PROVIDED	CAPACITY	PROVIDED
1.0-5.0 MIN./IN. (1)	22,381± S.F. OFFICE (2)	1,000 S.F. (3)(4)	150 L.F. OF GEOMATRIX GST3724 LEACHING SYSTEM W/ H-20 PROVISIONS	10.5 S.F./L.F.	1,575 S.F. (5)	1,500-GAL. (6)	2,000-GAL. (6)

(1) PERCOLATION TEST A IN THE LEACHING SYSTEM AREA WAS 4.0 MIN./IN. (SEE PERCOLATION TEST DATA ON THIS SHEET). (2) PROPOSED 22,381± S.F. MEDICAL OFFICE BUILDING.

(3) DESIGN FLOW = 1,000 GPD (ASSUMED METERED WATER USAGE OF A SIMILAR FACILITY) x 1.5 SAFETY FACTOR = 1,500 GPD (NOTE, 24,000± S.F. LAKEBROOK MEDICAL OFFICE BUILDING AT 5 PEQUOT PARK ROAD, WESTBROOK, CT HAS AN AVERAGE DAILY FLOW OF APPROX. 600 GPD BASED ON WATER METER DATA) (4) REQUIRED E.L.A. = 1,500 GPD (DESIGN FLOW) / 1.5 (APPLICATION RATE) = 1,000 S.F.

(5) E.L.A. PROVIDED =  $10.5 \text{ S.F./L.F.} \times 150 \text{ L.F.} = 1,575 \text{ S.F.}$ (6) REQUIRED SEPTIC TANK VOLUME = 1,500 GPD x 1 DAY = 1,500 GALLONS -- USE A SEPTIC TANK WITH A VOLUME OF 2,000-GALLONS

### MLSS COMPUTATIONS

DESIGN PERC RATE	# OF BEDROOMS	RECEIVING SOIL DEPTH	HYDRAULIC GRADIENT	HYDRAULIC FACTOR (HF)	FLOW FACTOR (FF)	PERCOLATION FACTOR (PF)	MLSS REQUIRED (HFxFFxPF)	MLSS PROVIDED
UP TO 10.0 MIN./IN. (1)	22,381± S.F. OFFICE (2)	36.1-42.0 INCHES (3)	2.1-3.0% (4)	30	5.0 (5)(6)	1.0	150 FT.	150 FT.

(1) PERCOLATION TEST A IN THE LEACHING SYSTEM AREA WAS 4.0 MIN./IN. (SEE PERCOLATION TEST DATA ON THIS SHEET).

(2) PROPOSED 22,381± S.F. MEDICAL OFFICE BUILDING. (3) RECEIVING SOIL DEPTH (IN SYSTEM AREA)= 10" (MIN. UNSATURATED NATURAL SOIL) 24" (MIN. SELECT FILL) + 24" (HEIGHT OF GEOMATRIX GST3724 LEACHING SYSTEM) = 58" RECEIVING SOIL DEPTH (DOWNGRADIENT) = 22" (MOTTLING DEPTH @ TP #203) + 19± (MOTTLING DEPTH @ TP #202) ] / 2 = 20.5"±

RECEIVING SOIL DEPTH (AVERAGE) =  $39.3"\pm --$  USE A RECEIVING SOIL DEPTH OF 36.1-42.0"

(4) HYDRAULIC GRADIENT = [ ELEV. 19.9± (MOTTLING @ TP #203) - ELEV. 18.3± (MOTTLING @ TP #202) ] / 62± L.F. = 2.6%± -- USE HYDRAULIC GRADIENT OF 2.1-3.0% (5) DESIGN FLOW = 1,000 GPD (ASSUMED METERED WATER USAGE OF A SIMILAR FACILITY) x 1.5 SAFETY FACTOR = 1,500 GPD

(NOTE, 24,000 ± S.F. LAKEBROOK MEDICAL OFFICE BUILDING AT 5 PEQUOT PARK ROAD, WESTBROOK, CT HAS AN AVERAGE DAILY FLOW OF APPROX. 600 GPD BASED ON WATER METER DATA) (6) FLOW FACTOR = 1,500 GPD (DESIGN FLOW) / 300 (APPLICATION RATE) = 5.0

### SANITARY SYSTEM PIPE INVERT TABLE

_	<u> </u>								
	STRUCTURE PIPE @ BUILDING		SEPTIC TANK	DISTRIBUTION BOX	LEACHING SYSTEM				
	INV. IN (FT.)		25.75 (1)	25.30	24.70				
	INV OUT (FT.)	26.00 (1)	25.50	25.20 (2)					

(1) PROPOSED 11.0± L.F. OF 4" SCH. 40 PVC ASTM D1785 BUILDING SEWER PIPE. PERCENT SLOPE =  $(26.00' - 25.75') \times 100\% / 11.0' \pm = 2.27\% \pm > 2.08\%$  (MIN.).

(2) INITIAL 10 FT. (MIN.) OF ALL DISTRIBUTION PIPES EXITING THE DISTRIBUTION BOX SHALL BE SET LEVEL FOR EVEN DISTRIBUTION.

(3) BOTTOM OF LEACHING SYSTEM SHALL BE SET LEVEL AND AT ELEVATION 22.70'.

(4) FOR ALL PIPE, A MIN. OF 12" OF COVER SHALL BE PROVIDED. (5) SEPTIC SYSTEM LABELS SHOWN FOR CLARITY (REFER TO SEPTIC SYSTEM KEY ON SHEET 3 OF 13).

STRUCTURE	PIPE @ BUILDING	SEPTIC TANK	DISTRIBUTION BOX	LEACHING SYSTEM
INV. IN (FT.)		25.75 (1)	25.30	24.70
NV. OUT (FT.)	26.00 (1)	25.50	25.20 (2)	

# FOR REVIEW - NOT FOR CONSTRUCTION

Approved by the Old Saybrook Zoning Commission

Title

Signature Date ESIGN CRITERIA 8

PREPARED FOR ORTHO
52 SPENCER PLAIN ROAD 

FOR ORTHO SAYBROOK, LI
RAP 25 LOT 27)
AYBROOK, CONNIC

DATA

APRIL 4, 2024 SCALE: AS NOTED DRAWN BY:

CHECKED BY:

DWG. NO.: SDC-1

SHEET NO .: 5 of 13 JOB. NO.:

2023-1030

#### <u>GENERAL NOTES (SEPTIC SYSTEM)</u>


- THE APPLICANT IS PROPOSING TO CONSTRUCT A 23,820± S.F 1-STORY MEDICAL OFFICE BUILDING WITH ASSOCIATED PARKING AND ACCESS DRIVE, INSTALL A 100% CONNECTICUT PUBLIC HEALTH CODE—COMPLIANT SEPTIC SYSTEM, STORMWATER MANAGEMENT AREA, AND OTHER ASSOCIATED IMPROVEMENTS.
- THIS PROPERTY IS SERVED BY PUBLIC WATER AND A SUBSURFACE SEWAGE DISPOSAL SYSTEM. THERE ARE NO KNOWN WELLS OR ANY OTHER KNOWN DESIGN CONFLICTS WITHIN 75 FEET OF THE PROPOSED SEPTIC SYSTEM.
- THE USE OF A GARBAGE DISPOSAL IS NOT RECOMMENDED. IF A GARBAGE DISPOSAL OR A TUB OVER 100 GALLONS IS INSTALLED, THE PROPOSED SEPTIC TANK SIZE SHALL BE INCREASED IN CONFORMANCE WITH THE PUBLIC HEALTH CODE. ANY WATER SOFTENER SHALL NOT DISCHARGE TO THE SEPTIC SYSTEM.
- THE PROPOSED BUILDING WILL BE CONSTRUCTED ON SLAB AND WILL NOT HAVE FOOTING DRAINS. THERE ARE NO KNOWN DOWNGRADIENT SEPTIC SYSTEM COMPONENTS WITHIN 25 FEET OF ANY UPGRADIENT GROUNDWATER DRAINS OR ANY UPGRADIENT SEPTIC SYSTEM COMPONENTS WITHIN 50 FEET OF ANY DOWNGRADIENT GROUNDWATER DRAINS.
- ALL UTILITIES SHALL BE INSTALLED IN CONFORMANCE WITH THE REQUIREMENTS AND SPECIFICATIONS OF THE TOWN OF OLD SAYBROOK AND THE CUSTODIAL UTILITY COMPANIES. ALL UTILITY TRENCHES SHALL BE NO LESS THAN 5 FEET FROM THE SEPTIC SYSTEMS AND NOT BACKFILLED WITH FREE DRAINING MATERIAL. ALL WATER LINES SHALL BE A MINIMUM OF 10 FEET FROM ANY PART OF THE SEPTIC SYSTEMS.

#### **GENERAL CONSTRUCTION NOTES (SEPTIC SYSTEM):**

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CURRENT CONNECTICUT PUBLIC HEALTH CODE, AS AMENDED.
- 2. A LICENSED SURVEYOR SHALL FIELD STAKE THE LOCATION OF THE PROPOSED SEPTIC SYSTEM PRIOR TO CONSTRUCTION AND SET A STABLE SITE BENCHMARK ON NAVD-88 DATUM (SAME AS SURVEY MAP).
- NO WORK SHALL COMMENCE IN THE SYSTEM AREA UNTIL A SEPTIC PERMIT HAS BEEN TAKEN OUT BY THE LICENSED INSTALLER.
- 4. THE LICENSED INSTALLER SHALL PERFORM SITE PREPARATION AND SHOULD CONTACT "CALL BEFORE YOU DIG" AT 1-800-922-4455 TO VERIFY ALL UTILITY LOCATIONS PRIOR TO ANY CONSTRUCTION.
- THE LICENSED INSTALLER SHALL BE ON SITE DURING SYSTEM CONSTRUCTION. THE SYSTEM SHALL BE INSTALLED IN CONFORMANCE TO THESE PLANS. ANY REQUESTED MODIFICATIONS SHALL BE DISCUSSED WITH THE ENGINEER PRIOR TO CONSTRUCTION. ALL MODIFICATIONS MUST BE APPROVED BY THE ENGINEER AND TOWN SANITARIAN PRIOR TO CONSTRUCTION.
- 6. A MINIMUM OF 24 HOURS NOTICE SHALL BE GIVEN BY THE LICENSED INSTALLER TO THE ENGINEER AND TOWN SANITARIAN BEFORE ANY STRIPPING IS DONE FOR THE SYSTEM. STRIP INSPECTIONS WILL BE PERFORMED BY THE ENGINEER AND
- THE LICENSED INSTALLER SHALL BE RESPONSIBLE FOR PREPARING THE LEACHING AREA IN A WORKMANLIKE MANNER. ALL NECESSARY STEPS SHALL BE TAKEN TO PROTECT THE UNDERLYING NATURALLY OCCURRING SOILS FROM OVER COMPACTION AND SILTATION ONCE EXPOSED.
- THE INSTALLER SHALL NOTIFY THE ENGINEER AND SANITARIAN AT LEAST 24 HOURS IN ADVANCE OF BEING READY FOR A FINAL INSPECTION. THE ENGINEER AND SANITARIAN SHALL CONDUCT THE FINAL INSPECTION TOGETHER WITH THE LICENSED INSTALLER. NO DEVIATION FROM THE PLAN APPROVED BY THE SANITARIAN SHALL BE ALLOWED WITHOUT PRIOR APPROVAL

FROM THE SANITARIAN. THE SYSTEM SHALL NOT BE BACKFILLED WITHOUT THE APPROVAL OF THE SANITARIAN.

- A LICENSED ENGINEER OR SURVEYOR SHALL PREPARE A SEPTIC SYSTEM AS-BUILT DRAWING CERTIFYING THE SYSTEM IS CODE-COMPLIANT. THIS PLAN SHALL INCLUDE ALL ESSENTIAL ACCESS POINTS INCLUDING TANK MANHOLES, DISTRIBUTION BOX AND LEACHING SYSTEM ENDS. THE AS-BUILT PLAN SHALL BE COMPLETED IN A TIMELY MANNER.
- 10. THE LEACHING SYSTEM SHALL BE PROPERLY COVERED BY THE LICENSED SYSTEM INSTALLER WITHIN TWO (2) WORKING DAYS FOLLOWING THE LOCAL HEALTH DEPARTMENT'S FINAL INSPECTION AND APPROVAL.
- 11. NO HEAVY EQUIPMENT SHALL BE DRIVEN OVER THE INSTALLED LEACHING SYSTEM AREA.
- 12. THE CONTRACTOR SHALL CONSULT WITH THE ENGINEER IF HE WISHES TO CHANGE THE LOCATION OR ELEVATION OF ANY PROPOSED SEPTIC SYSTEM COMPONENT PRIOR TO CONSTRUCTION.
- 13. THE LICENSED INSTALLER IS RESPONSIBLE TO INSTALL THE SUBSURFACE SEWAGE DISPOSAL SYSTEM IN ACCORDANCE WITH THE APPROVED PLAN.
- 14. THE SEPTIC TANK AND DISTRIBUTION BOX SHALL HAVE H-20 RISERS TO FINISHED GRADE. THE INSPECTION PORTS SHALL HAVE H-20 VALVE COVER ASSEMBLIES TO FINISHED GRADE. THE CONTRACTOR SHALL VERIFY SEPTIC TANK IS WATERTIGHT PRIOR TO
- 15. THE PROPOSED LEACHING SYSTEM, GEOMATRIX GST63724 (WITH H-20 PROVISIONS), SHALL BE INSTALLED IN CONFORMANCE WITH ALL MANUFACTURER'S SPECIFICATIONS. A GEOMATRIX SYSTEMS REPRESENTATIVE WILL DELIVER THE GEOMATRIX GST FORMS TO THE SITE AND WILL BE ON SITE DURING INSTALLATION OF THE SYSTEM TO ENSURE PROPER INSTALLATION. THE INSTALLER SHALL OBTAIN, REVIEW AND STRICTLY ADHERE TO THE ALL INSTALLATION INSTRUCTIONS AND MATERIAL SPECIFICATIONS. MORE INFORMATION CAN BE OBTAINED FROM THE MANUFACTURER, GEOMATRIX SYSTEMS, LLC - 114 MILL ROCK ROAD EAST, OLD SAYBROOK, CT - 860-510-0730 OR AT WWW.GEOMATRIXSYSTEMS.COM.
- 16. A TWO-PART CONCRETE SEPTIC TANK SHALL BE USED BUT MUST BE MADE 100% WATERTIGHT BY GASKETING AND MORTARING ALL JOINTS. IF A TWO-PART TANK IS USED, IT SHALL BE FILLED WITH WATER ABOVE THE JOINT AND INSPECTED BY THE ENGINEER AND/OR THE TOWN SANITARIAN WITHIN 24 HOURS. THE CONTRACTOR SHALL MONITOR THE WATER LEVEL IN THE TANK DURING THIS PERIOD AND SHALL PERMANENTLY REPAIR ANY LEAKS TO THE SATISFACTION OF THE ENGINEER AND THE TOWN SANITARIAN.
- 17. THE LICENSED INSTALLER SHALL CONFIRM THAT NO LEDGE IS PRESENT WITHIN 48 INCHES BELOW THE BOTTOM OF THE PROPOSED LEACHING SYSTEM.
- 18. THE CONTRACTOR SHALL GRADE THE AREA IN THE VICINITY OF THE LEACHING FIELD IN SUCH A MANNER THAT ALL SURFACE RUNOFF IS SUFFICIENTLY DIRECTED AWAY FROM THE LEACHING FIELD AREA AND NOT RESULT IN PONDING ON THE SUBJECT PROPERTY OR ANY ADJACENT PROPERTY OR ROADWAY.
- 19. THE LICENSED INSTALLER SHALL INCLUDE ALL ADEQUATE PROVISIONS FOR FREEZE PROTECTION FOR ALL PIPING AND
- 20. LICENSED INSTALLER SHALL PROVIDE SIEVE ANALYSES FOR C-33 SAND AND SELECT FILL PRIOR TO CONSTRUCTION.
- 21. THE CONTRACTOR SHALL FULLY COORDINATE WITH GEOMATRIX SYSTEMS, LLC (GEOMATRIX) AND SHALL ABIDE BY ALL SPECIFICATIONS AND INSTRUCTIONS FOR INSTALLATION OF THE GEOMATRIX GST6212 LEACHING SYSTEM. IT IS STRONGLY RECOMMENDED, ALTHOUGH NOT REQUIRED BY THE PUBLIC HEALTH CODE, TO INSTALL A SOILAIR SYSTEM ON THE PROPOSED LEACHING SYSTEM. AT A MINIMUM, SOIL AIR PIPING SHALL BE INSTALLED TO FACILITATE POTENTIAL FUTURE SOIL AIR BLOWER CONNECTIONS. IF SOIL AIR SYSTEM IS NOT INSTALLED, GEOMATRIX WILL REQUIRE OWNER TO SIGN A DISCLAIMER AGREEMENT.



<u>GEOMATRIX GST3724 LEACHING SYSTEM (WITH H-20 PROVISIONS) - PLAN VIEW</u>


# FILL AND GRADING NOTES (SEPTIC SYSTEM):

- 1. REMOVE ALL TOPSOIL AND/OR FILL WITHIN THE SYSTEM AREA AND SCARIFY THE SURFACE IN THE PROPOSED LEACHING SYSTEM AREA PRIOR TO PLACING ANY SELECT FILL MATERIAL. AVOID COMPACTING THE SCARIFIED AREA. FILL SHALL NOT BE PLACED OVER SNOW OR FROZEN GROUND. DISCONTINUE FILL PLACEMENT DURING HEAVY RAINFALL AND A MINIMUM OF 24 HOURS THEREAFTER. THE SELECT FILL MATERIAL SHALL BE PLACED IN 12" LIFTS AND COMPACTED TO 90% DENSITY.
- SELECT FILL MATERIAL SHALL CONSIST OF CLEAN SAND AND GRAVEL FREE FROM ORGANIC MATTER AND FOREIGN SUBSTANCES. THE SELECT FILL MATERIAL SHALL MEET THE REQUIREMENTS OF THE PUBLIC HEALTH
- CODE PROVIDED IN THE TABLE ON THIS SHEET. 3. THE LICENSED INSTALLER SHALL BE RESPONSIBLE FOR PREPARING THE LEACHING AREA UTILIZING THE SELECT FILL MATERIAL. 4. ALL NECESSARY STEPS SHALL BE TAKEN TO PROTECT THE UNDERLYING NATURALLY OCCURRING SOILS FROM OVER COMPACTION AND SILTATION
- ONCE EXPOSED. 5. THE CONTRACTOR SHALL PROVIDE GRADATION SPECIFICATIONS OF THE SELECT FILL MATERIAL TO BE USED FOR THE PROPOSED SEPTIC SYSTEM TO THE DESIGN ENGINEER AND TOWN SANITARIAN PRIOR TO ORDERING AND INSTALLATION.

#### SELECT FILL GRADATION TABLE

SIEVE SIZE		PERCENT PASSING			
		WET SIEVE	DRY SIEVE		
	#4	100	100		
	#10	70-100	70-100		
	#40	10-50*	10-75		
	#100	0-20	0-5		
	#200	0-5	0-2.5		
 	PERCENT PASS INCREASED TO PERCENT PASS EXCEED 10% A	NO GREATER THING THE #100 S	SIEVE CAN BE HAN 75% IF THE SIEVE DOES NOT SIEVE DOES NOT		

\*\* A SIEVE ANALYSIS FOR THE SELECT FILL MATERIAL SHALL BE PROVIDED TO THE <u>DESIGN</u> ENGINEER. ONLY THE <u>DESIGN</u> ENGINEER MAY APPROVE SELECT FILL MATERIAL NOT IN COMPLIANCE WITH THE GRADATION TABLE IF THE MATERIAL PASSING THE #200 SIEVE DOES NOT EXCEED 6% BASED ON WET



### CRUSHED AGGREGATE

**FABRIC** 

APPLICATIONS.

2. P = 2" TO 5.5"

PRESSURE APPLICATIONS.

GEOMATRIX SYSTEMS, LLC.

LESS THAN 10% FINES PASSING

PIPF (

CT DOT SEASON

APPROVED EQUIVALENT (SEE NOTE #3)

0.75" (MIN. I.D.) SCH. 40 ASTM D-1785 PVC PIPE FOR

1. 3" (MIN.) SCH. 40 ASTM D-1785 PVC PIPE FOR GRAVITY

3. 2" MINIMUM ASTM C-33 SAND OR APPROVED EQUIVALENT ON

4. PAVEMENT BASE AND SUBBASE (12" MIN. THICKNESS +

PAVEMENT) MAY BE ADEQUATE FOR H-20 LOADING. CONFIRM WITH

GEOMATRIX GST3724 LEACHING SYSTEM

(WITH H-20 PROVISIONS) - X-SECTION B-B


PERIMETER, BOTTOM AND SIDES OF SYSTEM.

2" MIN. ASTM C-33 SAND OR -

%#220 SIEVE (LOOSELY ROLLED)

		L GRADATION		PLUG SUPPLIED SYSTEMS, LLC
	SIZE	PERCENT PASSING		FEMALE ADAPTER
	1 1/2 IN.	100		BY GEOMATRIX S
	3/4 IN.	50-100		GEOMATRIX STIFFIE LLL OX L.F. SSIDOX 4" SCH. 40 AST
	#4	25-50		
	#40	10-20		AVHERE, C 10 600X  AVHERE, C 10 600X  SYSTEM) SUPPL
	#100	5–15		— DRAIN GRATE
	#200	LESS THAN 10		OF TEE SUPPL
SEE 'TYP	ICAL PAVEMENT —	1		GEOMATRIX SY
SECTION DETAIL' ON REQUIRED FOR			4" TEE SUPPLIED BY	
5	SHEET 7 OF 13	H-20 LOADING		GEOMATRIX SYSTEMS, LL
				NOTE: INSPECTION PORT ASSEMBLY SHALL BE H-2
SC MIN.	12" CRUSHED A	GGREGATE AUSUS		GEOMATRIX GST LEACHING
FILL OVER FABRIC - MAXIMUM TO				INSPECTION PORT DETA
PAI	RTICLE SIZE OF 1	1.5" AND 5		NOT TO SCALE

CUSTOM PLACARD THREADED ED BY GEOMATRIX TER SUPPLIED SYSTEMS, LLC ASTM D1785 NGTH BASED ON PLIED BY INSTALLER EACH SIDE PPLIED BY SYSTEMS, LLC -20 LOAD RATED <u>SYSTEM</u> NOT TO SCALE



FOR REVIEW - NOT FOR CONSTRUCTION

Approved by the Old Saybrook Zoning Commission


Title Date Signature

SCALE: NOT TO SCALE DRAWN BY: CHECKED BY: DWG. NO.: CD-1

APRIL 4, 2024

SAYBROOK, I (CT ROUTE. 27)


SHEET NO .: 6 of 13 JOB. NO .: 2023-1030



2. ALL MATERIALS AND CONSTRUCTION METHODS SHALL CONFORM TO CONNECTICUT DOT STANDARD SPECIFICATIONS FOR ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION FORM 818, 2020 OR AS AMENDED.


3. ALL UTILITIES SHALL BE INSTALLED IN ACCORDANCE WITH ALL TOWN OF OLD SAYBROOK AND CUSTODIAL UTILITY COMPANY SPECIFICATIONS. 4. ALL PROPOSED MATERIALS SHALL BE INSTALLED AS SHOWN OR AS APPROVED BY THE TOWN OF OLD SAYBROOK AND/OR CUSTODIAL UTILITY COMPANY.

### TYPICAL TRENCH DETAIL



UTILITY COMPANY SPECIFICATIONS. 4. ALL PROPOSED MATERIALS SHALL BE INSTALLED AS SHOWN OR AS APPROVED BY THE TOWN OF OLD SAYBROOK AND/OR CUSTODIAL UTILITY COMPANY. TYPICAL UNDERGROUND UTILITY TRENCH CROSS SECTION

SPECIFICATIONS FOR ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION FORM 818, 2020 OR AS AMENDED. 3. ALL UTILITIES SHALL BE INSTALLED IN ACCORDANCE WITH ALL TOWN OF OLD SAYBROOK AND CUSTODIAL




1. SELECT BACKFILL MATERIAL SHALL BE BANK-RUN GRAVEL GRADATION C, FORM 818, 2020, OR PROCESSED AGGREGATE CAN BE USED IN LIEU OF BANK-RUN GRAVEL OR APPROVED NATIVE MATERIAL. 2. ALL MATERIALS AND CONSTRUCTION METHODS SHALL CONFORM TO CONNECTICUT DOT STANDARD SPECIFICATIONS FOR ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION FORM 818, 2020 OR AS AMENDED.

3. ALL UTILITIES SHALL BE INSTALLED IN ACCORDANCE WITH ALL TOWN OF OLD SAYBROOK AND CUSTODIAL UTILITY COMPANY SPECIFICATIONS 4. ALL WORK WITHIN THE STREET RIGHT-OF-WAY SHALL CONFORM TO ALL APPLICABLE TOWN OF OLD

SAYBROOK AND/OR STATE REQUIREMENTS AND SPECIFICATIONS. 5. ALL PROPOSED MATERIALS SHALL BE INSTALLED AS SHOWN OR MATCH EXISTING CONDITIONS AS

APPROVED BY THE TOWN AND/OR D.O.T. INSPECTOR. 6. IF REINFORCED CONCRETE PAVEMENT IS ENCOUNTERED, THE CONTRACTOR SHALL COORDINATE WITH CONNECTICUT D.O.T. DISTRICT 2 FOR ANY SPECIAL REQUIREMENTS.


TYPICAL STATE ROADWAY TRENCH DETAIL



HANDICAPPED PARKING SIGN WITH 4" PAINTED STEEL CONCRETE FILLED BOLLARD (SEE DETAIL) FROM EDGE OF PAVEMENT (SEE SITE PLAN FOR LOCATION) -THIS LINE NOT REQUIRED IF LOCATED AT CURB WHITE LINES (TYP.) - HANDICAP SYMBOL TO BE PAINTED IN EACH SPACE 11' MIN. FOR STANDARD SPACE

8' MIN. FOR VAN ACCESSIBLE SPACE

8' MIN. V.A. 11' MIN. FOR STANDARD SPACE SINGLE OR DOUBLE HANDICAP SPACE HANDICAPPED PARKING STALL DETAIL NOT TO SCALE



SUBBASE MUST BE SHAPED AND PROPERLY COMPACTED PRIOR TO THE PLACEMENT OF BASE. ALL BRUSH, TREES AND ANY OTHER OBSTRUCTIONS SHALL BE CLEARED AND REMOVED FOR A DISTANCE OF 3 FEET BEYOND THE EDGE OF PAVEMENT ALONG BOTH SIDES FOR THE ENTIRE LENGTH OF THE DRIVEWAY. AND TO A HEIGHT OF 12 FEET ABOVE THE DRIVEWAY SURFACE. 3. ALL MATERIALS AND CONSTRUCTION METHODS SHALL CONFORM TO CONNECTICUT D.O.T. STANDARD


4. A 1-1/2" LIP AND A GRADUAL HUMP SHALL BE PROVIDED AS SHOWN TO PREVENT RUNOFF FROM ENTERING THE DRIVEWAY. THE DRIVEWAY HUMP SHALL BE 6" HIGH MINIMUM.


GRADUAL HUMP SHALL BE CONSTRUCTED IN A MANNER SO THAT STANDARD PASSENGER CARS CAN

EASILY TRAVERSE IT UPON ENTERING AND EXITING THE DRIVEWAY. 6. TACK COAT AND SEALER SHALL BE APPLIED BETWEEN ROADWAY AND DRIVEWAY APRON.


SPECIFICATIONS.


#### DESCENDING DRIVEWAY ENTRANCE DETAIL NOT TO SCALE





MAKE APPROPRIATE ADJUSTMENTS. TYPICAL PAVEMENT SECTION DETAIL





CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY ADEQUATE SUBGRADE CONDITIONS PRIOR TO PLACEMENT OF SUBBASE.


IF SHALLOW LEDGE IS ENCOUNTERED, CONTRACTOR SHALL CONSULT WITH DESIGN ENGINEER TO MAKE APPROPRIATE ADJUSTMENTS. CONTRACTOR SHALL PROVIDE SIEVE ANALYSES AND COMPACTION TESTING RESULTS FOR ALL BASE AND SUBBASE MATERIALS TO ENGINEER FOR REVIEW PRIOR TO PAVING


UNDERDRAIN SHALL BE INSTALLED BETWEEN CATCH BASINS AS DIRECTED BY THE DESIGN ENGINEER.

TYPICAL BOULEVARD STYLE DRIVEWAY ENTRANCE SECTION DETAIL


. IN NO CASE SHALL ANY UNDERDRAIN BE INSTALLED WITHIN 50 FEET OF ANY SEPTIC SYSTEM.

3500 PSI CONCRETE SLAB WITH (1) LAYER 6x6xW1.4xW1.4 WWF SEE "TYPICAL PAVEMENT SECTION DETAIL" ON THIS SHEET NOTE: ALSO SEE "CONCRETE SIDEWALK" DETAIL MONOLITHIC CONCRETE CURB DETAIL





CONCRETE SIDEWALK RAMP DETAIL NOT TO SCALE



### FOR REVIEW - NOT FOR CONSTRUCTION

Approved by the Old Saybrook Zoning Commission Title Date Signature

N DETAII SAYBROOK, L (CT ROUTE: ON CONSTRUCT
REPARED FOR OF
SPENCER PLAIN CON PR 52.9

APRIL 4, 2024

NOT TO SCALE

DRAWN BY:

CHECKED BY:

CD-2

7 of 13


2023-1030


DWG. NO.:


SHEET NO .:


JOB. NO.:


SCALE:
































FOR REVIEW -	NOT	F O R	CONSTRUCTION	V

Approved by the Old Saybrook Zoning Commission

Title Signature Date

				#	
CONSTRUCTION DETAILS (WATER)	PREPARED FOR ORTHO SAYBROOK, LLC	52 SPENCER PLAIN ROAD (CT ROUTE 166)	(MAP 25 LOT 27)	OLD SAYBROOK, CONNECTICUT	
DATE:		<u>ე</u> 24			
	APRIL 4, 2024 SCALE:				
NOT 1	NOT TO SCALE				
DRAW RG	DRAWN BY: RG				
CHECI JW	KED	BY:			
DWG.	NO.	•	CD	)-3	
SHEET		.: 3 (	of	13	

JOB. NO.:

2023-1030


#### SEED MIXTURE SCHEDULE


REFER TO LANDSCAPE PLAN ENTITLED "O&G INDUSTRIES, 52 SPENCER PLAIN RD., OLD SAYBROOK, CT", SCALE 1"=30', DATED: APRIL 18, 2024, PREPARED BY: J.W. FLYNN ASSOC. LLC.


#### STORMWATER MANAGEMENT BASIN CONSTRUCTION NOTES


SEDIMENT DEPTH MARKER INSTALLED TO MEASURE SEDIMENT DEPOSITION.


- AFTER ROUGH GRADING AND SHAPING, THE AREA OF THE BASIN SHALL BE MARKED OFF BY APPROPRIATE FENCING
  TO PREVENT THE MOVEMENT OF CONSTRUCTION VEHICLES OVER AND THE POSSIBLE OVER COMPACTION OF THE
  UNDERLYING NATURAL SOILS.
- 2. BASIN SHALL NEVER BE USED FOR SEDIMENT CONTROL DURING AN ACTIVE CONSTRUCTION PERIOD.
- 3. DURING CONSTRUCTION, SEDIMENT SHALL BE PREVENTED FROM ENTERING THE AREA OF THE BASIN. THE CONTRACTOR SHALL ENSURE THAT THE AREAS DRAINING TO THE BASIN ARE STABILIZED IN A TIMELY MANNER AND MAINTAINED OVER THE ENTIRE AREA DRAINING TO THE BASIN.
- 4. THE DESIGN ENGINEER SHALL MONITOR THE CONSTRUCTION OF THE STORMWATER MANAGEMENT BASIN, WILL PERFORM ALL FOLLOW UP INSPECTIONS, ASSESSMENTS AND REPORTS AND REMEDIATION WORK (IF NECESSARY) AND SHALL PROVIDE CERTIFICATION THAT THE SYSTEM WAS INSTALLED IN SUBSTANTIAL CONFORMANCE WITH THE APPROVED PLANS. A LICENSED LAND SURVEYOR SHALL PREPARE AN AS-BUILT OF THE CONSTRUCTED STORMWATER MANAGEMENT BASIN AREAS. THIS PLAN SHALL INCLUDE THE LOCATION AND INVERTS OF ANY ROOF DRAIN, DRAINAGE PIPE, CATCH BASIN AND OUTLET CONTROL STRUCTURE.
- 5. ALL DISTURBED AREAS SHALL BE FINE GRADED WITH 6" TOPSOIL, RAKED, SEEDED AND MULCHED IN A TIMELY MANNER. THE BOTTOM OF THE BASINS SHALL BE SEEDED PER THE PROJECT LANDSCAPE ARCHITECT.
- 6. FOREBAYS SHALL BE SIZED TO CONTAIN 100% OF THE WATER QUALITY VOLUME AND SHALL BE FORMED BY A BARRIER SUCH AS AN EARTHEN OR MODIFIED RIPRAP BERM. EACH FOREBAY SHALL ALSO HAVE A FIXED VERTICAL
- 7. REFER TO LANDSCAPE PLAN ENTITLED "O&G INDUSTRIES, 52 SPENCER PLAIN RD., OLD SAYBROOK, CT", SCALE 1"=30', DATED: APRIL 18, 2024, PREPARED BY: J.W. FLYNN ASSOC. LLC.
- 8. A BIOFILTRATION SOIL MIX SHALL BE INSTALLED ALONG THE ENTIRE BOTTOM OF STORMWATER MANAGEMENT BASIN #1. THE BIOFILTRATION MIX SHALL CONSIST OF 50-60% SAND, 20-30% TOPSOIL, AND 20-30% WEED-FREE LEAF COMPOST OR EQUIVALENT.




















FOR REVIEW - NOT FOR CONSTRUCTION

Approved by the Old Saybrook Zoning Commission

Title Signature Date



DETAILS
ORTHO SAYBROWN ROAD (CT ROAD (CT ROAD)
P 25 LOT 27)
OOK, CONNECT

ISTRUCTION
PREPARED FOR (52 SPENCER PLAII

APRIL 4, 2024

NOT TO SCALE

DRAWN BY:

CHECKED BY:

CD-4

9 of 13


2023-1030


DWG. NO.:

SHEET NO.:

JOB. NO.:


SCALE:








- 1. CONCRETE SIDEWALK THICKNESS AT DRIVEWAY CROSSINGS SHALL BE INCREASED TO 8 INCHES AND ADDITIONAL REINFORCEMENT PROVIDED AS REQUIRED BY TOWN. 2. ALL SIDEWALKS ALONG BOSTON POST ROAD (ROUTE 1) CORRIDOR WITHIN THE PEDESTRIAN NODE SHALL BE PORTLAND CEMENT CONCRETE, LINED WITH A BRICK SOLDIER COURSE OR COLORED, STAMPED CONCRETE IN CONFORMANCE WITH ZONING REGULATIONS SECTION 62 AND IN ACCORDANCE WITH THE CRITERIA AND STANDARDS SPECIFIED IN SECTIONS 70Q, 80M AND FIGURES 16 & 18 IN THE OLD SAYBROOK REGULATIONS FOR PUBLIC IMPROVEMENTS.
- 3. THE CONTRACTOR SHALL COORDINATE ALL SIDEWALK CONSTRUCTION WITH THE DIRECTOR OF 4. CONCRETE SHALL BE TYPE "F", AIR ENTRAINED. STEEL DOWELS SHALL BE PROVIDED AT ALL
- EXPANSION JOINTS. 5. SIDEWALKS SHALL BE STENCILED, NOT IMPRINTED. ALL SIDEWALK CONSTRUCTION MATERIALS AND METHODS INCLUDING STENCILING PATTERN AND COLORING SHALL CONFORM TO THE SPECIFICATIONS FOR THE "OLD SAYBROOK SIDEWALKS".

# ROADWAY CONCRETE SIDEWALK DETAIL NOT TO SCALE









### FOR REVIEW - NOT FOR CONSTRUCTION

Approved by the Old Saybrook Zoning Commission

Title Signature

CONSTRUCTION DETAILS
PREPARED FOR ORTHO SAYBROOK, LLC
52 SPENCER PLAIN ROAD (CT ROUTE 166)
(MAP 25 LOT 27)
OLD SAYBROOK, CONNECTICUT

APRIL 4, 2024 SCALE: AS NOTED


DRAWN BY: CHECKED BY:

DWG. NO.: CD-4

SHEET NO .: 10 of 13

JOB. NO.: 2023-1030

Date



#### SOIL EROSION & SEDIMENTATION CONTROL PLAN NARRATIVE

THE SITE CONTRACTOR MUST FOLLOW ALL GUIDELINES SET FORTH IN THE MANUAL ENTITLED "CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL", PUBLISHED SEPTEMBER 30, 2023, REVISED MARCH 26, 2024 OR AS AMENDED, BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEPARTMENT OF ENVIRONMENTAL PROTECTION.

THE APPLICANT IS PROPOSING TO CONSTRUCT A 23,820± S.F 1-STORY MEDICAL OFFICE BUILDING WITH ASSOCIATED PARKING AND ACCESS DRIVE, INSTALL A 100% CONNECTICUT PUBLIC HEALTH CODE-COMPLIANT SEPTIC SYSTEM. STORMWATER MANAGEMENT AREA, AND OTHER ASSOCIATED IMPROVEMENTS

CONSTRUCTION IS ANTICIPATED TO COMMENCE IN SPRING 2024. ALL EROSION AND SEDIMENT CONTROLS SHALL BE INSTALLED PRIOR TO CONSTRUCTION ACTIVITIES. E & S CONTROLS SHALL BE MAINTAINED AND REPAIRED OR REPLACED AS NEEDED THROUGHOUT THE CONSTRUCTION DURATION. ALL E & S CONTROLS SHALL BE REMOVED AND PROPERLY DISPOSED OF AS SOON AS THE SITE IS COMPLETELY STABILIZED.

- I. CONTACT "CALL BEFORE YOU DIG" TO MARK OUT ALL UTILITY LOCATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.
- ENSURE ALL LAND USE PERMITS HAVE BEEN SECURED. OBTAIN ALL NECESSARY PERMITS. LAND SURVEYOR TO STAKE OUT CLEARING LIMITS & PROPOSED IMPROVEMENTS.
- INSTALL ALL EROSION AND SEDIMENT CONTROLS AND CONSTRUCTION ENTRANCE. REMOVE ALL TREES, BRUSH AND STUMPS WITHIN CLEARING LIMITS.
- STRIP AND STOCKPILE TOPSOIL AND OTHER EXCAVATED SOILS IN AREA(S) SHOWN ON PLAN. APPLY TEMPORARY SEED MIXTURE TO PILES IF THEY WILL NOT BE DISTURBED FOR MORE THAN 30 DAYS. IMPORT AND SPREAD FILL TO ROUGH GRADE AND PREPARE SEPTIC AND STORMWATER MANAGEMENT AREAS AS REQUIRED.
- ROUGH GRADE DRIVEWAY AND PARKING AREA. 9. CONSTRUCT STORMWATER MANAGEMENT BASIN.
- 10. CONSTRUCT THE FOUNDATION FOR THE PROPOSED BUILDING.
- 1. FRAME AND CONSTRUCT THE PROPOSED BUILDING. 12. INSTALL ALL UTILITIES AND SEPTIC SYSTEM.
- 13. FINISH GRADE DRIVEWAY AND PARKING AREA AND PAVE PER PLAN (BINDER COURSE ONLY). 14. FINISH GRADE, SEED AND MULCH ALL DISTURBED AREAS AS REQUIRED.
- 15. INSTALL ALL LANDSCAPING AND LIGHTING POLES/FIXTURES.
- 16. INSTALL SURFACE COURSE PAVEMENT AND STRIPE PARKING LOT. 17. REMOVE ALL EROSION AND SEDIMENT CONTROLS ONCE SITE IS COMPLETELY STABILIZED. DISPOSE OF PROPERLY.
- I. ALL EXISTING VEGETATION OUTSIDE OF THE CLEARING LIMITS SHALL BE PROTECTED. EXISTING VEGETATION SHALL BE REMOVED ONLY IN AREAS NECESSARY FOR SITE CONSTRUCTION ACTIVITIES. ANY ADDITIONAL CLEARING OUTSIDE OF THE PROPOSED CLEARING LIMITS SHALL BE APPROVED BY TOWN STAFF PRIOR TO CLEARING. ALL AREAS SHALL REMAIN UNDISTURBED UNTIL IMMEDIATELY PRIOR TO SITE DEVELOPMENT.
- ALL CONSTRUCTION EQUIPMENT, MATERIALS AND STOCKPILES SHALL NOT BE PLACED OUTSIDE OF THE DISTURBED AREAS. ALL TREES, BRUSH, STUMPS, WOOD CHIPS OR OTHER ORGANIC MATTER SHALL BE DISPOSED OF PROPERLY OFF-SITE. WOOD CHIPS MAY BE USED AS A SILTATION BARRIER DURING CONSTRUCTION AND SPREAD AFTER SITE IS STABILIZED. NO ORGANIC MATTER INCLUDING TREES, BRUSH AND STUMPS SHALL BE BURIED ON-SITE.

STRIPPING AND STOCKPILING ALL STOCKPILES THAT CONSIST OF ERODIBLE MATERIALS SHALL BE LOCATED WITHIN AREAS AS SHOWN ON THE SITE PLAN AND SURROUNDED BY A SILTATION BARRIER. ANY STOCKPILE THAT WILL REMAIN UNDISTURBED FOR A PERIOD LONGER THAN 30 DAYS SHALL BE SEEDED WITH A TEMPORARY GRASS SEED MIXTURE TO PREVENT EXCESSIVE EROSION AND SEDIMENTATION.

TRENCH EXCAVATION AND BACKFILL THE CONTRACTOR SHALL PROPERLY MAINTAIN ALL BACKFILLED EXCAVATIONS. ANY DEPRESSIONS DUE TO SETTLING IN THESE AREAS SHALL BE FILLED AND RESEEDED AS NECESSARY.

THE WIDTH OF ALL EXCAVATED TRENCHES SHALL BE KEPT AS NARROW AS PRACTICABLE TO ACCOMMODATE THE WORK. ALL MATERIALS EXCAVATED FROM TRENCHES SHALL BE STOCKPILED AND USED AS TRENCH BACKFILL MATERIAL UNLESS IT IS DETERMINED TO BE UNSUITABLE BY THE ENGINEER. EXCESS MATERIALS SHALL BE PROPERLY DISPOSED OF BY THE CONTRACTOR. SOIL EROSION AND SEDIMENT CONTROLS

ALL ADJACENT PROPERTIES AND RECEIVING WATERCOURSES AND / OR WETLAND AREAS SHALL BE ADEQUATELY PROTECTED FROM SOIL EROSION AND SEDIMENTATION BOTH DURING AND AFTER CONSTRUCTION. ADDITIONAL EROSION AND SEDIMENT CONTROLS MAY BE REQUIRED BY THE TOWN AND SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROLS BEFORE, DURING AND AFTER CONSTRUCTION. THE CONTRACTOR IS ALSO RESPONSIBLE FOR THE PROPER REMOVAL AND DISPOSAL OF ALL

ALL EROSION AND SEDIMENT CONTROLS SHALL BE INSPECTED WEEKLY AND AFTER ALL RAINFALL EVENTS. E & S CONTROLS SHALL BE REPAIRED OR REPLACED AS NECESSARY WITHIN 24 HOURS THROUGHOUT THE

IF NECESSARY, A TEMPORARY FILTER FABRIC SILT BARRIER SHALL BE PLACED BENEATH THE GRATE OF THE PROPOSED CATCH BASIN TO PREVENT ANY SILTATION OF THE DRAINAGE SYSTEM. THE FILTER FABRIC SHALL BE REMOVED IMMEDIATELY AFTER THE SURROUNDING AREAS ARE ADEQUATELY STABILIZED.

ALL ACCUMULATED SEDIMENTS AT ALL EROSION AND SEDIMENT CONTROLS SHALL BE PERIODICALLY REMOVED AND SPREAD IN AREAS THAT ARE NOT SUBJECT TO EROSION. THE CONTRACTOR SHALL EMPLOY BEST MANAGEMENT PRACTICES TO CONTROL STORMWATER DISCHARGES AND TO PREVENT EROSION AND SEDIMENTATION AND TO OTHERWISE PREVENT POLLUTION OF WETLANDS OR WATERCOURSES OR PRIVATE PROPERTY. THE CONTRACTOR SHALL IMMEDIATELY INFORM THE TOWN OF ANY PROBLEMS INVOLVING EROSION AND/OR SEDIMENTATION THAT HAVE DEVELOPED IN THE COURSE OF, OR THAT

ARE CAUSED BY, THE AUTHORIZED WORK. THE RESPONSIBLE CONTACT PERSON FOR THE INSTALLATION AND MAINTENANCE OR EROSION AND SEDIMENTATION CONTROLS ON THIS PROJECT WILL BE THE SITE CONTRACTOR AND / OR THE GENERAL CONTRACTOR. ONCE THE GENERAL CONTRACTOR IS SELECTED, CONTACT INFORMATION WILL BE PROVIDED TO THE TOWN. VEGETATIVE TURF ESTABLISHMENT PROCEDURE

SCARIFY ALL AREAS TO BE TOPSOILED AND SEEDED. APPLY A MINIMUM OF 4 INCHES OF TOPSOIL ON ALL AREAS TO BE SEEDED. APPLY GRASS SEED, LIME, FERTILIZER AND MULCH ACCORDING TO THE FOLLOWING

PERMANENT SEED MIXTURE: CREEPING RED FESCUE 0.90 LBS. PER 1,000 SQ. FT.

EROSION AND SEDIMENT CONTROLS ONCE THE SITE IS COMPLETELY STABILIZED.

0.90 TALL FESCUE TOTAL

10-10-10 APPLY AT 7.5 LBS. PER 1,000 SQ. FT.

APPLY AT 150 LBS. PER 1,000 SQ. FT. MUI CHING:

SPREAD HAY OR STRAW OVER ALL AREAS AFTER SEEDING. USE 1 1/2 TO 2 BALES PER 1,000 SQ. FT. TARGET FOR 100% COVERAGE. ANCHOR BY USING NETTING OR TRACKING AS NECESSARY.

TEMPORARY EROSION CONTROL BLANKETS:

USE TEMPORARY EROSION CONTROL BLANKETS ON ALL SEEDED SLOPES STEEPER THAN 3 (H) TO 1 (V) AND/OR AS DIRECTED BY THE DESIGN ENGINEER.


SEEDING DATES IN CONNECTICUT ARE NORMALLY APRIL 1 THROUGH JUNE 15 AND AUGUST 15 THROUGH OCTOBER 1. SEED GERMINATION NORMALLY CANNOT BE EXPECTED FROM NOVEMBER THROUGH FEBRUARY, IF ADEQUATE SEED GERMINATION IS NOT POSSIBLE DUE TO TIME OF YEAR CONSTRAINTS, MULCHING SHALL BE ADEQUATELY PROVIDED TO PROTECT THE SEED FROM WIND AND SURFACE EROSION UNTIL THE WEATHER IMPROVES AND THE SEEDING BECOMES WELL ESTABLISHED.

DRAINAGE SYSTEM MAINTENANCE

IT SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER TO MAINTAIN THE DRAINAGE SYSTEM AND STORMWATER MANAGEMENT BASINS TO ENSURE PROPER FUNCTION AND EFFICIENT OPERATION. PARKING LOTS, AND ACCESS DRIVES SHALL BE SWEPT AND ALL TRASH CLEANED UP ON AN AS NEEDED BASIS. ALL CATCH BASINS SHALL BE CLEANED OF SEDIMENT AND TRASH ON A SEMI-ANNUAL BASIS - IN THE FALL AFTER THE LEAVES HAVE FALLEN FROM TREES AND IN THE SPRING. REFER TO "STORMWATER PONDS AND WETLANDS" CHECKLIST ON THIS SHEET FOR DETAILED MAINTENANCE REQUIREMENTS FOR STORMWATER MANAGEMENT BASINS.

#### Mitigation and Restoration Sequence and Plan Notes

- 1. All sedimentation and erosion controls will be established before grading begins.
- 2. Temporary devices and structures to control erosion and sedimentation in and around mitigation sites shall be properly maintained at all times. The devices and structures shall be disassembled and disposed of no later than November 1, three full growing seasons after planting. Sediments collected by these devices will be removed and placed upland in a manner that prevents its transport into a wetland or waterway.
- 3. Construction of mitigation will take place before the driveway retaining walls have been constructed. Access will be through the upland on the north side of the existing entrance.
- 4. Topsoil will be stripped from the impact area and stockpiled on site for later re-use in the mitigation area if necessary.
- 5. The mitigation area will be over excavated 1.0 feet below the final elevations if deemed necessary by the on-site wetland scientist as shown on the plan and refilled to the specified grades with topsoil. The on-site wetland scientist will establish microtopographic grading.
- 6. All wetland mitigation areas will be seeded with New England Wetmix (New England Plants, Inc, Amherst. MA, ph 413-256-1752) or equivalent at 1 lb per 2500 s.f.
- 7. Planting and seeding will take place in the spring or fall planting periods to maximize plant survival and seed germination. The mitigation area will be planted prior to the construction of the driveway retaining walls. The restoration of temporary disturbance to wetland and upland around the retaining walls will be completed after the retaining walls are completed.
- 8. A supply of dead and dying woody debris shall cover at least 2% of the ground throughout the mitigation site after completion of construction of the mitigation site. These materials should not include species shown on the attached list of invasive species.
- 9. No equipment will be staged in the existing wetlands. All bulky waste and garbage will be removed by hand labor. Equipment will be used in the mitigation area only as necessary for removal of fill and grading. If necessary construction mats will be used to stage equipment.
- 10. To reduce the immediate threat and minimize the long-term potential of degradation, the species included on the Connecticut invasive plant species list are not included as planting stock in the overall project. Only plant materials native and indigenous to the region shall be used. Species not specified in the mitigation plan shall not be used without written approval from the
- 11. A certified soil scientist or qualified wetland scientist will over-see the mitigation work .A certified soil scientist or qualified wetland scientist will locate the sites for planting the
- 12. The site will be monitored for 3 years following the completion of work and controlled for invasive species. Annual reports will be filed with the Local Inland Wetlands Commission. The standards for survival of the plantings shall be as follows: The minimum survival standard will be 80% of woody plantings. At the end of each growing season a count of the shrubs and trees will be conducted. If less than 80% survival occurs, the dead vegetation will be replaced during the next planting season with new live plantings to bring the live plantings to above 80%.
- 13. The Local Inland Wetlands Commission will be notified before work begins and also be notified upon completion of the mitigation site and plantings so that they may inspect.



	Mitigation Area Planting Schedule				Eastern Wetland Buffer		
Name	NWI Wetland Indicator Status	Quantity	Size	Name	NWI Wetland Indicator Status	Quantity	Size
Shrubs				Shrubs			
Winterberry holly ( <i>Ilex</i> verticillata))	Facultative Wetland	10	1 gallon	Red chokeberry (Aronia arbutilfolia)	Facultative Wetland	45	1 gallor
Arrowood vibunum (Viburnum recognitum)	Facultative Wetland (-)	10	1 gallon	Arrowood vibunum (Viburnum dentatum)	Facultative Wetland (-)	45	1 gallor
Highbush blueberry( <i>Vaccinum</i> <i>corymbosum</i> )	Facultative Wetland	10	1 gallon	Witch hazel (Hamamelis virginia)	Facultative Wetland	45	1 gallor
Plants				Spicebush (Lindera benzoin)	Facultative Wetland (-)	45	1 Gallo
Fowl Manna Grass ( <i>Glyceria canadensis</i> )	Obligate	50	plugs	Seedmixe			
Tussock sedge (Carex stricta)	Obligate	50	plugs	New England Conservation Wildlife Mix	Variable		
Canada rush ( <i>Juncus</i> canadensis)	Obligate	50	plugs				

FOR REVIEW - NOT FOR CONSTRUCTION New England Wetmix Variable

Approved by the Old Saybrook Zoning Commission Title Date Signature

OOK, I

NARRA-ONTROL PREPARED F


APRIL 4, 2024

SCALE: NOT TO SCALE DRAWN BY: CHECKED BY:

DWG. NO. ES-1

SHEET NO .: 11 of 13

JOB. NO : 2023-1030




#### **ELEVATION**

- 1. USE 12 INCH OR LARGER DIAMETER CORRUGATED METAL, HDPE, OR PVC PIPE WITH 1 INCH DIAMETER PERFORATIONS, 6 INCHES ON CENTER. BOTTOM OF PIPE MUST BE CAPPED WITH WATERTIGHT SEAL.
- WRAP PIPE WITH 1/4 INCH GALVANIZED HARDWARE CLOTH AND WRAP NONWOVEN GEOTEXTILE, AS SPECIFIED IN SECTION H-1 MATERIALS, OVER THE HARDWARE CLOTH.
- 3. EXCAVATE PIT TO THREE TIMES THE PIPE DIAMETER AND FOUR FEET IN DEPTH. PLACE 3/4 TO 11/2 INCH STONE OR EQUIVALENT RECYCLED CONCRETE, 6 INCHES IN DEPTH PRIOR TO PIPE PLACEMENT.
- 4. SET TOP OF PIPE MINIMUM 12 INCHES ABOVE WATER SURFACE ELEVATION.
- 5. BACKFILL PIT AROUND THE PIPE WITH 3/4 TO 11/2 INCH CLEAN STONE OR EQUIVALENT RECYCLED CONCRETE AND EXTEND STONE A MINIMUM OF 6 INCHES ABOVE ANTICIPATED WATER SURFACE ELEVATION.
- 6. DISCHARGE TO A STABLE AREA AT A NONEROSIVE RATE.

CONSTRUCTION SPECIFICATIONS

- 7. A SUMP PIT REQUIRES FREQUENT MAINTENANCE. IF SYSTEM CLOGS, REMOVE PERFORATED PIPE AND REPLACE GEOTEXTILE AND STONE. KEEP POINT OF DISCHARGE FREE OF EROSION.
- \* THIS DETAIL ONLY REQUIRED FOR DEWATERING DURING CONSTRUCTION IF SHALLOW GROUNDWATER IS ENCOUNTERED.

### SUMP PIT DETAIL



#### CONSTRUCTION SPECIFICATIONS

SEAM STRENGTH

- 1. TIGHTLY SEAL SLEEVE AROUND THE PUMP DISCHARGE HOSE WITH A STRAP OR SIMILAR DEVICE.
- 2. PLACE FILTER BAG ON SUITABLE BASE (E.G., MULCH, LEAF/WOOD COMPOST, WOODCHIPS, SAND, OR STRAW BALES) LOCATED ON A LEVEL OR 5% MAXIMUM SLOPING SURFACE. DISCHARGE TO A STABILIZED AREA. EXTEND BASE A MINIMUM OF 12 INCHES FROM EDGES OF BAG.
- 3. CONTROL PUMPING RATE TO PREVENT EXCESSIVE PRESSURE WITHIN THE FILTER BAG IN ACCORDANCE WITH
- THE MANUFACTURER RECOMMENDATIONS. AS THE BAG FILLS WITH SEDIMENT, REDUCE PUMPING RATE. REMOVE AND PROPERLY DISPOSE OF FILTER BAG UPON COMPLETION OF PUMPING OPERATIONS OR AFTER BAG HAS REACHED CAPACITY, WHICHEVER OCCURS FIRST. SPREAD THE DEWATERED SEDIMENT FROM THE BAG IN AN APPROVED UPLAND AREA AND STABILIZE WITH SEED AND MULCH BY THE END OF THE WORK DAY. RESTORE THE SURFACE AREA BENEATH THE BAG TO ORIGINAL CONDITION UPON REMOVAL OF THE
- 5. USE NONWOVEN GEOTEXTILE WITH DOUBLE STITCHED SEAMS USING HIGH STRENGTH THREAD. SIZE SLEEVE TO ACCOMMODATE A MAXIMUM 4 INCH DIAMETER PUMP DISCHARGE HOSE. THE BAG MUST BE MANUFACTURED FROM A NONWOVEN GEOTEXTILE THAT MEETS OR EXCEEDS MINIMUM AVERAGE ROLL VALUES


(MARV) FOR THE FOLLOWING:	OLOTEXTICE THAT MILETO ON EXOLESS	WINNING WITH THE TOTAL THE
GRAB TENSILE	250 LB	ASTM D-4632
PUNCTURE	150 LB	ASTM D-4833
FLOW RATE	70 GAL/MIN/FT <sup>2</sup>	ASTM D-4491
PERMITTIVITY (SEC <sup>-1</sup> )	1.2 SEC <sup>-1</sup>	ASTM D-4491
UV RESISTANCE	70% STRENGTH @ 500 HOURS	ASTM D-4355
APPARENT OPENING SIZE (AOS)	0.15-0.18 MM	ASTM D-4751

6. REPLACE FILTER BAG IF BAG CLOGS OR HAS RIPS, TEARS, OR PUNCTURES. DURING OPERATION KEEP CONNECTION BETWEEN PUMP HOSE AND FILTER BAG WATER TIGHT. REPLACE BEDDING IF IT BECOMES

ASTM D-4632

- \* FILTER BAG SHALL BE PLACED NO CLOSER THAN 25' TO ANY WETLAND AREA OR DOWNGRADIENT PROPERTY
- \* THIS DETAIL ONLY REQUIRED FOR DEWATERING DURING CONSTRUCTION IF SHALLOW GROUNDWATER IS ENCOUNTERED.

### <u>FILTER BAG DETAIL</u>




#### PLAN VIEW


- 1. APPLY TEMPORARY SEED MIXTURE TO PILES IF THEY WILL NOT BE DISTURBED FOR MORE THAN 30 DAYS.
- 2. ALL SILT FENCE SHALL BE INSPECTED PERIODICALLY AND AFTER ALL RAINFALL EVENTS. REPAIRS SHALL BE MADE IMMEDIATELY TO KEEP THE SILTATION CONTROL BARRIER EFFECTIVE.

STOCKPILE SILTATION CONTROL DETAIL

100' MIN. 'MINIMUM CONNDOT GRADATION No. 3 STONE FILTER FABRIC REMOVE TOPSOIL AND ORGANICS BEFORE PLACING FILTER FABRIC AND ANGULAR STONE. 2. REDRESS STONE THROUGHOUT CONSTRUCTION AS NEEDED. CONSTRUCTION ENTRANCE DETAIL









- EROSION CONTROL BLANKETS SHALL CONSIST OF BIODEGRADABLE MATERIALS TEMPORARY EROSION CONTROL BLANKETS SHALL BE PROVIDED ON ALL 3:1 SLOPES OR STEEPER. CONTRACTOR SHALL PREPARE SURFACE, REMOVE PROTRUDING OBJECTS AND INSTALL TEMPORARY
- EROSION CONTROL BLANKETS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS. 4. CONTRACTOR SHALL ENSURE THE ORIENTATION AND ANCHORING OF THE BLANKET IS APPROPRIATE FOR THE SITE.
- 5. CONTRACTOR SHALL INSPECT THE TEMPORARY EROSION CONTROL BLANKET AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH RAINFALL OF 0.5 INCHES OR MORE. IF WASHOUT OR BREAKOUT OCCURS, CONTRACTOR SHALL RE-INSTALL THE BLANKET AFTER REGRADING AND RE-SEEDING THE AREA.


EROSION CONTROL BLANKET DETAIL






TYPICALLY, SEDIMENT TRAPS ARE REQUIRED FOR ANY DISCHARGE POINT THAT SERVES AN AREA BETWEEN 2 AND 5 DISTURBED ACRES OF LAND. ALL TEMPORARY SEDIMENT TRAPS SHALL BE DESIGNED IN CONFORMANCE WITH THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL". GENERALLY TEMPORARY SEDIMENT TRAPS SHALL BE SIZED TO PROVIDE A MINIMUM OF 154 CUBIC YARDS OF WATER STORAGE PER ACRE DRAINED. ALL TEMPORARY SEDIMENT TRAPS SHALL BE MAINTAINED TO ASSURE EFFICIENT OPERATION UNTIL THE CONTRIBUTING AREA IS COMPLETELY STABILIZED. TEMPORARY SEDIMENT TRAPS MAY BE RELOCATED DURING CONSTRUCTION TO ACCOMMODATE PHASING. CONTRACTOR SHALL REVIEW LOCATIONS OF TEMPORARY SEDIMENT TRAPS WITH DESIGN ENGINEER PRIOR TO INSTALLATION. NO TEMPORARY SEDIMENT TRAP SHALL HAVE MORE THAN 5 ACRES OF DISTURBED LAND CONTRIBUTING TO IT.


#### TEMPORARY SEDIMENT TRAP




- CONTRACTOR SHALL PREPARE SURFACE, REMOVE PROTRUDING OBJECTS AND INSTALL TEMPORARY EROSION CONTROL BLANKETS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS.
- 2. CONTRACTOR SHALL ENSURE THE ORIENTATION AND ANCHORING OF THE BLANKET IS APPROPRIATE 3. CONTRACTOR SHALL INSPECT THE TEMPORARY EROSION CONTROL BLANKET AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH RAINFALL OF 0.5 INCHES OR MORE. IF WASHOUT OR BREAKOUT OCCURS, CONTRACTOR SHALL RE-INSTALL THE BLANKET AFTER REGRADING AND RE-SEEDING THE AREA
  - EROSION CONTROL BLANKET DETAIL

4. ALL EROSION CONTROL BLANKETS SHALL CONSIST OF BIODEGRADABLE MATERIALS.








### FOR REVIEW - NOT FOR CONSTRUCTION

Approved by the Old Saybrook Zoning Commission Title Date Signature



ROOK, I

 $\infty$ 

ES-2 SHEET NO .: 12 of 13 JOB. NO : 2023-1030

#### **CLA Engineers, Inc. CLA Engineers, Inc. CLA Engineers, Inc. CLA Engineers, Inc.** Civil • Structural • Survey 317 MAIN STREET • NORWICH-C1 06360 • (860) 886-1966 • (860) 886-9165 FAX 317 MAIN STREET • NORWICH, CT 06360 • (860) 886-1966 • (860) 886-9165 FAX 317 MAIN STREET • NORWICH, CT 06360 • (860) 886-1966 • (860) 886-9165 FAX 317 MAIN STREET • NORWICH, CT 06360 • (860) 886-1966 • (860) 886-9165 FAX. Permeability of Soils using Compaction Permeameter Date: 9/23/2022 Project: Indigo Land Design CLA Project #: 7154 Source: Spencer Plains Road, Old Saybrook, Ct. Material: On-site material (Test Pits) SIEVE ANALYSIS SIEVE ANALYSIS SIEVE ANALYSIS Specification: 100 lbs/cu ft Compaction on samples Date: 9/1/2022 Date: 9/19/2022 Date: 9/19/2022 Project: Spencer Plains Road, Old Saybrook, Ct. CLA Project #: 7154 Project: Spencer Plains Road, Old Saybrook, Ct. Project: Spencer Plains Road, Old Saybrook, Ct. CLA Project #: 7154 Sample #1: Test Pit # Sample A CLA Project#: 7154 Source: Old Saybrook, Ct. Source: Old Saybrook, Ct. Source: Old Saybrook, Ct. Material: On-site material (Test Pits) Material: On-site material (Test Pits) Material: On-site material (Test Pits) Permeability: 2.22 x 10-4 cm/sec or .62 ft/day Specification: N/A Specification: N/A Specification: N/A Sample #1: Test Pit # Sample B Sample Designation: Test Pit # Sample A Sample Designation: Test Pit # Sample B Sample Designation: Test Pit # Sample B2 Permeability: 1.85 x 10-4 cm/sec or .52 ft/day % Passing Sieve Size % Passing % Passing Sieve Size 3/4 in 3/4 in 98.1 94.5 3/4 in Sample #1: Sample B2 1/4 in 99.9 93.3 90.8 $\frac{1}{4}$ in #4 92.2 99.183.2 Permeability 2.78 x 10-4 cm/sec or .78 ft/day 65.9 94.1 88.1#10 58.7 45.9 83.2 80.1#20 76.3 64.047.7 31.3 Thomas Cummings 23 56-22 34.5 36.7 20.5 PE No. 9606 23.3 25.2 10.5 Thomas Cummings 23500 22 Thomas Cummings 2550922 Thomas Cummings 23 Sep 22 PE No. 9606 PE No. 9606 PE No. 9606 MOISTURE DENSITY SIEVE ANALYSIS (4" Mold) SIEVE ANALYSIS SIEVE ANALYSIS 9/1 & 9/2/2022 CLIENT: Indigo Land Design Indigo Land Design Indigo Land Design 9/19/2022 PROJECT: 52 Spencer Plains Road, Old Saybrook, Ct. PROJECT: PROJECT: 52 Spenver Plains Road, Old Saybrook, Ct. PROJECT: 52 Spenver Plains Road, Old Saybrook, Ct. 52 Spenver Plains Road, Old Saybrook, Ct. SAMPLE: SOURCE: SOURCE: SAMPLING METHOD: Sampled on site SAMPLING METHOD Sample + Pan - Pan Weight + Sample SAMPLING METHOD SAMPLING METHOD Gross Weight Sieve Weight Weight 0.179 0.021 /dry 11.7 Net Weight 6.950 3/4 in 3/4 in 3/4 in \_ 10.2 \_ 0.0 5.802 =4.126 1.676 /0.033 = 50.79 50.79 1111.73 /1.MC= 100.0 1/4 in 46.6 1/4 in 0.4 0.1 99.9 1/4 in 35.2 #4 #4 5.2 0.9 41.2 Sample + Pan - Pan Weight + Sample 7.8 16.8 #10 173.4 34.2 5.9 94.1 #10 63 11.9 34.1 65.9 0.200 #20 210.2 #20 96.6 16.8 #20 104.8 19.9 41.3 83.2 80.1 58.7 0.180 M/C 11.11 #40 275 136.6 23.7 #40 189.6 76.3 36.0 64.0 54.1 45.9 0.020 /dry 11:1 #60 349.2 #60 310.8 #60 275.6 53.9 52.3 46.1 68.7 31.3 Net Weight #100 404.2 377.4 #100 65.5 34.5 #100 333.8 63.3 36.7 79.5 20.5 #200 453.6 5.792 -4.126 = 1.666 / 0.033 = 50.48 \*2.2 = 1111.07 /1.M/C = 100.0 442 #200 76.7 23.3 #200 394.4 74.8 25.2 89.2 10.8 Full Mold Weight - Mold = Net Weight 508.6 576.4 527.2 Sample + Pan - Pan Weight + Sample 0.200 0.186 M/C 7.53 7.5 Net Weight 5.739 -4.126 = 1.613 /0.033 = 48.88 2.2 = 107.53 /1.MC= 100.0 Sample + Pan - Pan Weight + Sample SAMPLE #4 #DIV/0! -4.126 - 4.126 / 0.033 - -125.03 \*2.2 - -275.07 /1.M/C= Full Mold Weight - Mold = Net Weight Sample + Pan - Pan Weight + Sample #DIV/0! #DIV/0! Net Weight -4.126 /0.033 = -125.05 -2.2 -275.07 /1 M/C= #DIV/0 Full Mold Weight - Mold = Net Weight M:\7000\7100\7154 52 Spencer Plains Rd\Material Testing\7154 - Spencer Plains Road - TP #82 9 - 19 = 2022 Ns M:\7000\7100\7154 52 Spencer Plains Rd\Material Testing\7154 - Spencer Plains Road - MoistureDensity-4Mold 9 - 1 - 2022 xis M:\7000\7100\7154 52 Spencer Plains Rd\Material Testing\7154 - Spencer Plains Road - TP #A 9 - 1 - 2022 xis M:\7000\7100\7154 52 Spencer Plains Rd\Material Testing\7154 - Spencer Plains Road - TP #B 9 - 19 - 2022 xls

FOR REVIEW - NOT FOR CONSTRUCTION

Approved by the Old Saybrook Zoning Commission

Title Signature CHECKED BY: DWG. NO.: SSD-1 SHEET NO .: 13 of 13 JOB. NO.:

2023-1030

OIL SAMPLE DATA
ED FOR ORTHO SAYBROOK, LI
CER PLAIN ROAD (CT ROUTE 1
(MAP 25 LOT 27)
) SAYBROOK, CONNECTICUT

SOIL PREPARED FC 52 SPENCER PI

APRIL 4, 2024

NOT TO SCALE

DRAWN BY:

SCALE:

Date